BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20426

SCHEDULE-B

NAME OF WORK: Providing pothole filling at W.no.12 Shetty halli Sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor G N RAMESH		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	289.62	77.96	Rupees Seventy Seven and Ninety Six Paise Only	22578.78
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specfication & as per direction of Engineer-in-charge	Cum	308.53	1606.84	Rupees One Thousand Six Hundred Six and Eighty Four Paise Only	495758.35
3	Filling Pot-Holes and patch repairs with Bituminous Concrete, 40mm., KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specfication & as per direction of Engineer-in-charge	Sqm	1148.16 1148.2	347.29	Rupees Three Hundred Forty Seven and Twenty Nine Paise Only	398744.49

Signature of the Contractor

Executive Engineer

4	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	289.62	68.17	Rupees Sixty Eight and Seventeen Paise Only	19743.40
					Total	936825.00
					Percentage	-6.25%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer